

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 40-25

LOCATION CS 1/2 SW SW

SEC. 36 TWP. 10 RGE. 16

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. A-2 Lease Gish

Operator Cities Service Co Address Great Bend, Kans

Field _____ County Rooks

Total Depth 3548 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 240' circulated with cement - 5 1/2" at 3548' with
200 sax cement behind - drilled plug to 3518' - perforations at
3217'.

Set Halliburton plug at 3200', set sand and 5 sax cement with dump
bailer, pulled 2550' 5 1/2", filled hole with mud to 240', set
rock and 15 sax cement, mud to 35', set rock and 10 sax
cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
9-25-52
SEP 25 1952

Edwin Perry
District Conservation Agent

PLUGGING
FILE SEC 36 T 10 R 16
BOOK PAGE 16 LINE 23

CONSERVATION DIVISION
Wichita, Kansas Date 9-22-52