

15-163-20440-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-12-72
JUN 12 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Northridge Oil & Robert Bryne

Complete Address Box 18217 Denver, Colorado

Lease Name Zeigler Well No. 1

Location C S/2 S/2 SE Sec 34 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3620'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated _____

Plugging Contractor H 30, Inc.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 3:4 Day 8 Month 6 Year 1972

The above well was plugged as follows:

RTD 3620' 8 5/8 csg set at 250' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 6-13-72
INV. NO. 5859-W