

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-11-68
JUL 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Co. Inc.,

Complete Address: 1425 Wichita Plaza Wichita, Kansas

Lease Name Bowlby "A" Well No. 1

Location SE SW NE Sec. 1 Twp. 11 Rge. 16 (E) (W) X

County Ellis Total Depth 3520

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling

Address: Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 11 A Day 8 Month 7 Year 1968

The Above well was plugged as follows:

Total Depth 3520' 8 5/8 csg set at 215' cwc.

4 1/2 csg set at 3277' cw 150 sc cement.

4 1/2 csg PBTD 3270' with top perf. at 3158'

Filled 4 1/2 csg with sand (3270-3140) and dumped 4 sc cement with dump bailer (3140-3100)

Recov. 2500' of 4 1/2 csg.

Pumped thru 4 1/2 plg. container with 25 sc gel & water, W/5 sc hulls, Plug and 130 sc

50-50 poz cement W/6% total gel. Max pres. 300 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 7/12/68
INV. NO. 8082-W