

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE NW

SEC. 5 TWP. 11 RGE. 16 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Ramey

Operator E. D. Bradstreet Address Russell, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 50'8 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 198' circulated with cement - 5 1/2" at 3000' with  
150 sax cement behind - Lane Wells plugs to 3238' - perforated  
5190'.

Sand to 3180', set 4 sax cement with dump bailer, pulled 2400'  
5 1/2" - mud to 190', set rock and 15 sax cement, mud to 30',  
set rock and 10 sax cement to bottom cellar.

2-18-54

[Signature]  
District Conservation Agent

Date 2-10-54

**PLUGGING**  
FILE SEC 3 T 11 R 16W  
BOOK PAGE 14 LINE 21