

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-23-70
APR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Phillips Petroleum Company

Complete Address Box 287 Great Bend, Kansas 67530

Lease Name Nettie Unit Well No. 10 -#2

Location SW NE SE Sec. 4 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3494 3560

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor _____

Address _____ License No. _____

Operation Completed: Hour 5P Day 21 Month 4 Year 1970

The above well was plugged as follows:

Total Depth ³⁵⁶⁰ 3494' 8 5/8 csg set at 190' cwc

5 1/2 csg set at 3560' cw 300 sk cmt.

5 1/2 csg PBTB 3494' with perf. (3400-3464)

5 1/2 csg bad at 970' No pipe recovered.

Displace 50 sk comm. cmt W/2% cc at 970' thru tubing.

Circ. 7 sk gel W/3 sk hulls at 500' thru tubing.

Circ. 40 sk comm. cmt. at 220' thru tubing. — Ran wire line top of cmt. 289'.

Filled (open end) with 35 sk comm cmt to base of cellar.

Pumped down annulus (8 5/8 - 5 1/2) with 50 sk cmt. to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/23/70

INV. NO. 1778-12