

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
CONSERVATION COMMISSION  
11-21-66  
NOV 21 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Kohlus of Birmingham-Bartlett has this date requested permission to plug the following described well:

Mr. Kohlus guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drilling Company

Complete Address: 300 Kaufman Bldg. Wichita, Kansas

Lease Name: Bowlby Well No. 4

Location: C-1 1/2 NE SW Sec. 1 Twp. 11 Rge. 16 (E)(W) X

County Ellis Total Depth 3344' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Kohlus was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
25 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/3 sc hulls and 8 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

[Signature]  
Conservation Division Agent