



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

15-167-21931-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1982

VERBAL PERMIT FORM

(To be filed by Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ben Griffen of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: E.S.P. Development

Complete Address: 1/2 Lewis Eulert, Paradise, Ks. 67658

Lease Name: Veh Well No. 1

Location: Nw SE NW Sec. 17 Twp. 11 Rge. 15 (E) (W)

County: Russell Total Depth: 3475'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXX

Other well as hereafter indicated: _____

Mr. Griffen was instructed to plug the well as follows:

8 5/8" S.P. cuc. w/150 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel. 3% Cal.Cl. & 8 5/8" Plug

Spot w/drill stem w/heavy mud between all plugs.


1st plug @ 660' w/70 sacks cement

2nd plug @ 230' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement

Circulate 10 sacks in rat hole.

Very truly yours,


Conservation Division Agent