



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-16724608-00-00

Dear Sir:

Mr. Weiler of Shields Drlg. has this

date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas 67665

Lease Name: Nancy Well No. 1

Location: NE NE NW Sec. 18 Twp. 11 Rge. 15 (E) (W)

County: Russell Total Depth: 3528'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A  X

Other well as hereafter indicated: \_\_\_\_\_

Mr. Weiler was instructed to plug the well as follows:

Fill hole with mud and spot 60 sx cement at 660'.

Fill hole with mud and spot 30 sx cement at 250'.

Fill hole with mud to 40' & 1/2 sx hulls, plug, & 10 sx cem.

5 sx cem. in rat hole. 5 sx cem. in mouse hole.

250' of 8 5/8" surface casing cement circ.

Very truly yours,

JAN 20 1981  
01-29-1981  
CONSERVATION DIVISION  
Wichita, Kansas

Duane Rankin  
Conservation Division Agent