

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION MAR 20 1974 03 20 1974 CONSERVATION DIVISION Wichita, Kansas

15-195-20265-00-00

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Nierenberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Nierenberger guarantees payment of the plugging fee.

Operator's full Name: Ben J. Tepper & Joe Katz db/a Katz Oil A/C,

Complete Address: 420 South Dixie, Coral Gables, Florida.

Lease Name: Shearer Well No. 1

Location: SW-SE-SW Sec. 13 Twp. 11 Rge. (E)(W) 25

County: Trego Total Depth 3989' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

239'--8 5/8" Surface casing, cement circulated with 175 Sx. Top of Dakota section @ 800'.

Circulate hole with heavy mud. Pull DP to 1025' and displace 110 Cu. Ft. cement thru DP. Pull DP to 250' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols Conservation Division Agent