

15-063-21451-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev.03/92

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-063-21,451 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Abercrombie Drilling, Inc. KCC LICENSE # 5422  
(owner/company name) (operator's)

ADDRESS 150 N. Main, Suite 801 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-1841

LEASE Johnson Trust WELL# #1 SEC. 10 T. 11S R. 31 (East/West)

- NE - NW - NW SPOT LOCATION/QQQQ COUNTY Gove

330' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

990' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 283' CEMENTED WITH 60-40 posmix-175 sx SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 2995'/3000' T.D. 4737' PSTD \_\_\_\_\_ ANHYDRITE DEPTH 2540' (+460')  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2560' w/25 sx; 2nd plug @ 1700' w/100 sx; 3rd plug @ 330' w/40 sx; 4th plug @ 40' w/10 sx; rathole 15 sx; Total 185 sx 60-40 posmix 6% gel 2 sx celoflake in mix.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin PHONE# (913) 743-5443

ADDRESS 533 N. Main, City/State Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684  
(company name) (contractor's)

ADDRESS 150 N. Main, Suite 801 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Complete @ 12:15 p.m. 5-21-93.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-3-93 AUTHORIZED OPERATOR/AGENT: Jack K. Whastor  
(signature)

RECEIVED  
STATE CORPORATION COMMISSION  
8-4-1993  
AUG - 4 1993