

Amended

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior INC
Address 1: P.O. Box 399
Address 2:
City: Garden City State: KS Zip: 67846
Contact Person: Kevin Wiles Sr
Phone: (620) 275-2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: SWD Permit #:
 ENHR Permit #: Gas Storage Permit #:
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 4742 Bottom: 4770 T.D. 4869
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API No. 15-033-20,162-0000
name 03/25
C-SW Sec. 28 Twp. 31 S. R. 16 East West
4080/1256 Feet from North / South Line of Section
140/4021 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Comanche
Lease Name: Schuette Well #: 3
Date Well Completed: 10-31-1974
The plugging proposal was approved on: 2-5-09 (Date)
by: Eric Maclaren, District One (KCC District Agent's Name)
Plugging Commenced: 2/12/09
Plugging Completed: 2-13-09
2/13/09

Resdist PRT KA

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	357'	None
		Production	4-1/2"	4868'	1700'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Hook-up to 4-1/2" csg. pump 25 sks cem. & 300#s hulls, waited 1 Hr. csg. on vac. pump 40 sks cem. & 300#s hulls, press 200#s, cut off csg. @ 2225' pull to 1000' pump 50 sks Cem. & 12 sks Gel. Latch onto Csg. " stuck in hole", SD. 12-13-09 cut csg. off @ 506', pull csg to 360'. pump 50 sks. Cem. cement circulated, pull rest of csg. top off csg. w/ 20 sks cem. (Cement 60/40 pos. 4% gel) wash up, cut off csg. 6' below GL. Fill cellar.

KANSAS CORPORATION COMMISSION

MAY 14 2009
RECEIVED

Plugging Contractor License #: 32382 33645 Name: Swift Services INC
Address 1: P.O. Box 466 Address 2:
City: Ness City State: KS Zip: 67560
Phone: (785) 798-2300
Name of Party Responsible for Plugging Fees: American Warrior INC
State of Kansas County, Finney
Kevin Wiles Sr / Production Supt. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PRT