

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: John O. Farmer, Inc.
Address: P.O. Box 352, Russell, KS 67665
Phone: (785) 483-3145 ext. 214 Operator License #: 5135
Type of Well: D & A (SIOW) Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-24,767-0000
Lease Name: McJunkin Unit
Well Number: 1
Spot Location (QQQQ): SE - NE - SE - SE
840 Feet from North / South Section Line
150 Feet from East / West Section Line
Sec. 5 Twp. 20 S. R. 21 East West
County: Ness
Date Well Completed: _____
Plugging Commenced: 04/21/09
Plugging Completed: 04/22/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8 "	689'	
				5 1/2 "	4454'	2730'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Raised hole, Checked hole, Sanded off bottom, Loaded hole with water, Dug cellar, Unpacked casing head, Set Floor, Pulled slips, Had 24" stretch, Swedge in, Bailed 5 sacks of portland, Ripped 2901', No gain, Ripped 2838', No gain, Ripped 2730', Worked free, Pulled to 1470', Well flowed oil, Pumped 15 gel, 1 hull, 50 sacks, Pulled to 720', Pumped 50 sacks, Pulled to 300', Pumped 40 sacks, Pulled to 40', Pumped 20 sacks, Tore down, Loaded out, Pushed oil into cellar.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526
Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.
State of Kansas County, Russell, ss.


John O. Farmer III (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 6th day of May, 2009

Margaret A. Schulte My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS CORPORATION COMMISSION
MAY 08 2009
RECEIVED

Handwritten initials

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 3000

Date	Sec.	Twp.	Range	County	State	On Location	Finish
4/22/07	5	20	21	NEES	KS		S 308m
Lease	Well No. 2		Location				
Contractor: Quality Well Service				Owner			
Type Job: Plug & Abandon				To Quality Oilwell Cementing, Inc.			
Hole Size				You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Csg. 5 1/2				Charge To J. O. Farmer			
Tbg. Size				Street			
Drill Pipe				City State			
Tool				Depth			
Cement Left in Csg.				The above was done to satisfaction and supervision of owner agent or contractor.			
Press Max.				Shoe Joint			
Meas Line				Minimum			
Perf.				Displace			
EQUIPMENT							
Pumptrk 7	No.	Cementer	Amount Ordered 160 7/10 430 gal				
		Helper	Common 45 @ 10 460.00				
Bulktrk 10	No.	Driver	Poz. Mix 64 @ 6 384.00				
		Driver	Gel. 21 @ 17 357.00				
Bulktrk 24	No.	Driver	Calcium				
		Driver	Mills 4 @ 16.5 @ 25 125.00				
JOB SERVICES & REMARKS							
Pumptrk Charge PTA				500.00			
Mileage 22 @ 6.00				132.00			
Footage							
Total				632.00			
Remarks:				Handling 186 @ 1.75 325.50			
				Mileage 84 @ 2.50 210.00			
				Pump Truck Charge			
FLOAT EQUIPMENT							
				Guide Shoe			
				Centralizer			
				Baskets			
				AFU Inserts			
				Rotating Head			
				Squeez Mainfold			
X Signature				Tax 128.60			
				Discount (607.00)			
				Total Charge 2559.10			

Thank you

Quality Oilwell Cementing