

15-109-20090-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Logan County, Sec. 8 Twp. 11 Rge. 32W (E) (W)

Location as "NE/CNWxSWx" or footage from lines. NW SW NE

Lease Owner Donald C. Slawson

Lease Name Schippers 'B' Well No. 1

Office Address 200 Douglas Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed September 17 19 77

Application for plugging filed September 17 19 77

Application for plugging approved September 17 19 77

Plugging commenced September 17 19 77

Plugging completed September 17 19 77

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation Depth to top Bottom Total Depth of Well 4697 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	325	surface	323'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 1600' w/70 sx
2nd plug @ 300' w/40 sx
Top plug @ 40' w/10 sx
2 sx in rat hole

10-18-1977
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Co., Inc.

Address 200 Douglas Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.J. Thatcher, 200 Douglas Building

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 77

My commission expires 11/9/80

Margene Hamer

Notary Public.



WELL LOG

OPERATOR: Donald C. Slawson
 200 Douglas Building
 Wichita, Kansas 67202

LEASE: #1 Schippers 'B'
 NW SW NE Sec. 8-11-32W
 Logan County, Kansas

CONTRACTOR: Slawson Drilling Co., Inc.

COMMENCED: September 6, 1977

COMPLETED: September 17, 1977

CASING: 8 5/8" @ 323' w/200 sx 60/40 poz

0 - 325 Surface hole
 325 - 1875 Shale and shells
 1875 - 2375 Shale and sand
 2375 - 2378 Shale
 2378 - 2590 Shale and shells
 2590 - 2620 Anhydrite
 2620 - 2683 Shale and shells
 2683 - 4053 Shale and lime
 4053 - 4108 Lime
 4108 - 4152 Lime and shale
 4152 - 4390 Lime
 4390 - 4562 Shale and Lime
 4562 - 4626 Lime
 4626 - 4697 Lime and shale
 4697 RTD

RECEIVED
 STATE CORPORATION COMMISSION
 10-18-1977
 OCT 18 1977
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, R.J. Thatcher, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Schippers 'B' test.

R.J. Thatcher

 R.J. Thatcher

Subscribed and sworn to before me this 14th day of October, 1977.

MarGene Hamer

 MarGene Hamer, Notary Public

NOTARY PUBLIC
 MARGENE HAMER
 Sedgwick County, Ks.
 My Appt. Exp. 11-9-80