

15-109-20026-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Logan SEC. 12 TWP. 11 RGE. 32 E/W
 Location as in quarters or footage from lines:
 C/SW/NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Pickrell Drilling
 Lease Name City of Oakley Well No. #1
 Office Address Box 1303 - Great Bend, Ks. 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced September 9, 1983
 Plugging completed September 16, 1983
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation _____ Depth to top _____ bottom T.D. 4641'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	284'	NONE
				4 1/2"	4633'	1628.86'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped four (4) sacks cement on bottom, sanded to 4050' and dumped
 four (4) sacks cement.
 Shot casing at 3000', 2500', 2000', 1800' and 1600'.
 Pulled forty-nine (49) joints 4 1/2" casing.
 Sun squeezed well with two (2) sacks hulls, fifteen (15) sacks gel,
 one hundred (100) sacks cement, twenty-five (25) sacks gel, released plug
 and pumped seventy (70) sacks 50/50 pozmix cement with 6% added gel
 and 3% calcium chloride. Maximum pressure was 500 psi.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 19th day of Sept., 1983



Margaret Prosser
 Notary Public.

My Commission expires:

RECEIVED
 STATE CORPORATION COMMISSION
 9-20-1983
 SEP 20 1983
 CONSERVATION DIVISION
 Wichita, Kansas