

15-109-00016-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

0			

Locate well correctly on above
Section Plat

Logan County. Sec. 12 Twp. 11 Rge. 32 (X) (W)
Location as "NE/CNW/SWK" or footage from lines NW NW NW
Lease Owner William Gruenerwald et al
Lease Name Swart Well No. 1
Office Address 35 East Wacker Drive, Chicago, Illinois
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed January 23, 19 56
Application for plugging filed January 23, 19 56
Application for plugging approved January 23, 19 56
Plugging commenced January 23, 19 56
Plugging completed January 23, 19 56
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4765' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	236	8 5/8"	236'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy rotary mud from 4765' back to 200'. One Howco plug, one-half sack of hulls, and 15 sacks cement placed through drill pipe. Heavy rotary mud from plug to 40'. One Howco plug, one-half sack hulls, and 15 sacks cement.

WELL
STATE CORPORATION COMMISSION
2-20-1958
FEB 20 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor BUICK DRILLING INC.
Address P. O. Box 331, St. John, Kansas

STATE OF Kansas COUNTY OF Stafford, ss.
H. R. Buick (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. R. Buick*
P. O. Box 331, St. John, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1956

Roberta Shogren
Notary Public.

My commission expires December 26, 1959

PLUGGING
FILE SEC 12 T 11 R 32 W
BOOK PAGE 34 LINE 30

15-109-00016-00-00

DRILLERS LOG

Swart #1	NW NW NW Sec. 12-11-32W
Commenced R.D.: 1-5-56	Logan County, Kansas
Completed R.D.: 1-23-56	Elevation: 3046' D.F.
Total Depth: 4765'	Initial Prod.: None
Casing Record: 236', 8 5/8"	Contractor: Buick Drilling Inc.

STRATA	DEPTH
Clay	0 - 33
Sand	33 - 38
Clay	38 - 92
Sand	92 - 155
Shale and clay	155 - 182
Sand and gravel	182 - 186
Shale	186 - 236
Shale and shells	236 - 998
Chalk and lime	998 - 1080
Shale	1080 - 1420
Sand	1420 - 1490
Shale and shells	1490 - 1780
Shale	1780 - 1850
Sandy lime, iron pyrite, and shale breaks	1850 - 2037
Anhydrite	2037 - 2073
Yellow clay	2073 - 2155
Clay and red bed	2155 - 2178
Anhydrite	2178 - 2220
Red Bed	2220 - 2275
Anhydrite	2275 - 2285
Red bed	2285 - 2305
Anhydrite	2305 - 2315
Red bed and shale	2315 - 2558
Anhydrite	2558 - 2590
Red bed, shale and shells	2590 - 3330
Red bed, shale and chert	3330 - 3410
Sand, shale and chert	3410 - 3470
Shale and chert	3470 - 3520
Shale and lime	3520 - 4010
Lime	4010 - 4240
Lime and shale	4240 - 4330
Lime	4330 - 4405
Lime and shale	4405 - 4490
Lime	4480 - 4547
Lime and shale	4547 - 4590
Lime	4590 - 4615
Lime and shale	4615 - 4670
Lime	4670 - 4765 T.D.

2-20-1956

CONST
W

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

H. R. Buick, President

Signed and sworn to in my presence this 24th day of January, 1956, by H. R. Buick, President of the Buick Drilling Inc.

Notary Public

My commission expires Dec. 26, 1959.

PLUGGING
 FILE SEC 12 11 32W
 BOOK PAGE 34 LINE 30