

15-109-20354-00-00

API NUMBER 109-20,354-00-00

LEASE NAME Betsy Lee

WELL NUMBER #1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 14 TWP. 11S RGE. 32 (X) or (W)

COUNTY Logan

Date Well Completed 1-19-85

Plugging Commenced 6-23-85

Plugging Completed 6-24-85

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Solar Petroleum, Inc.

ADDRESS 1099 18th St. Suite 2900 Denver, Colorado 80202

PHONE# (303) 292-5850 OPERATORS LICENSE NO. 6879

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation none Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|------|-------|--------|------------------|
| | | surf | 344 | 8 5/8 | 344 | -- |
| | | | 4749 | 5 1/2 | 4749 | cut off at 1100' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

SEE REVERSE SIDE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address PO Box 31 Russell, Kansas

STATE OF Colorado COUNTY OF Denver, ss.

Solar Petroleum, Inc.

(Employee of Operator) of _____

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Marie O'Keefe

(Address) 1099 18th St. Ste 2900 Denver, Co80202

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 85

Petta Daniel
 Notary Public

My Commission Expires: August 22, 1987

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 28 1985
 6-28-1985
 CONSERVATION DIVISION
 WICHITA, KANSAS

4750 TD

4695 PBDT

8 5/8 @ 344' w/225 sx

5 1/2 @ 4749' w/150 sx

Top of cement 4030

Set cast iron BP @ 4120; 75 sx on top w/dmp boiler. Cut pipe 3942, could not pull out @ 2500'. Left cable head & magnetic collar counter in the hole @ 2174. Cut off pipe @ 1100'.

RU Allied Cement plugged w/3 sx hulls, 20 sx gel, 100 sx cement & 1 sk hulls, 20 sx gel, 8 5/8" wiper plug, 8 sx cement.

All cement 50/50 poz 6% gel.

Plug down @ 9:50 a.m., 6-24-85

State inspector Carl Goodrow, witnessed plugging.