

MAY 17 2007

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

5/15/09

CONSERVATION DIVISION  
WICHITA, KS

Operator: License # 4058  
Name: American Warrior, Inc.  
Address: P. O. Box 399  
City/State/Zip: Garden City, KS 67846  
Purchaser: N/A  
Operator Contact Person: Joe Smith  
Phone: (620) 275-2963  
Contractor: Name: Murfin Drilling Company  
License: 30606  
Wellsite Geologist: Jim Dilts

CONFIDENTIAL

KCC

MAY 15 2007

CONFIDENTIAL

Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SIOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back  Plug Back Total Depth  
 Commingled  Docket No. \_\_\_\_\_  
 Dual Completion  Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?)  Docket No. \_\_\_\_\_

3-4-07	3-17-07	3-26-07
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 025-21,405-00-00  
County: Clark  
SE SE SE Sec. 19 Twp. 30 S. R. 23  East  West  
330 FSL feet from S / N (circle one) Line of Section  
480 FEL feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW SW  
Lease Name: Esplund CD & E Well #: 4-19  
Field Name: Wildcat

Producing Formation: None  
Elevation: Ground: 2416' Kelly Bushing: 2427'  
Total Depth: 5650' Plug Back Total Depth: 5312'  
Amount of Surface Pipe Set and Cemented at 709 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from \_\_\_\_\_  
feet depth to \_\_\_\_\_ w/ \_\_\_\_\_ sx cmt.

Drilling Fluid Management Plan PA NH 10-2708  
(Data must be collected from the Reserve Pit)  
Chloride content 11,000 ppm Fluid volume 320 bbls  
Dewatering method used Hauled Off Site

Location of fluid disposal if hauled offsite:  
Operator Name: American Warrior, Inc.  
Lease Name: Taylor (B) 2 SWD License No.: 4058  
Quarter SW Sec. 17 Twp. 30 S. R. 23  East  West  
County: Clark Docket No.: D-19,490

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: \_\_\_\_\_  
Title: Compliance Coordinator Date: 5-15-07

Subscribed and sworn to before me this 15<sup>th</sup> day of May, 2007.

Notary Public: Erica Kuhlmeier  
Date Commission Expires: 09/20/09  
My Appt. Expires 09/20/09

**KCC Office Use ONLY**  
 Letter of Confidentiality Received  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

Operator Name: American Warrior, Inc. Lease Name: Esplund CD & E Well #: 4-19  
 Sec. 19 Twp. 30 S. R. 23  East  West County: Clark

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken  Yes  No  
 (Attach Additional Sheets)

Samples Sent to Geological Survey  Yes  No

Cores Taken  Yes  No

Electric Log Run  Yes  No  
 (Submit Copy)

List All E. Logs Run:

Sonic Cement Bond Log

Log Formation (Top), Depth and Datum  Sample

Name Top Datum  
 No Geo Report

KCC  
 MAY 15 2007  
 CONFIDENTIAL

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface Pipe	12-1/4"	8-5/8"		709'	Common	225 sx	3% cc 2% Get
		5-1/2"	15.5#	5350'	SMD	150 SX	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input checked="" type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone	N/A			

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	5102' TO 5111'	2500 Gal 15% NE RECEIVED KANSAS CORPORATION COMMISSION	
		MAY 17 2007	
		CONSERVATION DIVISION WICHITA, KS	

TUBING RECORD	Size	Set At	Packer At	Liner Run
				<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No


Date of First, Resumerd Production, SWD or Enhr.	Producing Method
	<input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	N/A	N/A	N/A		

Disposition of Gas  Vented  Sold  Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION  Open Hole  Perf.  Dually Comp.  Commingled  Other (Specify) Dry Hole

Production Interval \_\_\_\_\_



CHARGE TO: *American Warrior Inc*

ADDRESS

CITY, STATE, ZIP CODE

TICKET  
Nº 11462

PAGE 1 OF 2

*Suby  
Pay.*

SERVICE LOCATIONS 1. <i>Hays, Ks</i>	WELL/PROJECT NO. <i>CD &amp; F #4-19</i>	LEASE <i>Espland Farms</i>	COUNTY/PARISH <i>Clarke</i>	STATE <i>Ks</i>	CITY	DATE <i>3-18-07</i>	OWNER <i>Same</i>
2. <i>Ness City, Ks</i>	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR <i>Murfin Drlg #22</i>	RIG NAME/NO.	SHIPPED VIA <i>ET</i>	DELIVERED TO <i>Location</i>	ORDER NO.	
3.	WELL TYPE <i>Gas</i>	WELL CATEGORY <i>Development</i>	JOB PURPOSE <i>Cement Longstring</i>	WELL PERMIT NO.	WELL LOCATION		
4.	REFERRAL LOCATION	INVOICE INSTRUCTIONS					

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UM		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE #103	100	mi			4.00	400.00
578		1			Pump Charge (Longstring)	1	ea			1250.00	1250.00
280		1			Flocheck 21	750	gal			2.75	2062.50
402	RECEIVED KANSAS CORPORATION COMMISSION MAY 17 2007 CONSERVATION DIVISION WICHITA KS	1			Centralizers	8	ea	5 1/2"		80.00	640.00
403		1			Basket	2	ea			280.00	560.00
405		1			Formation Packer Shoe	1	ea			1400.00	1400.00
406		1			L.D. Plug & Baffle	1	ea			235.00	235.00

**LEGAL TERMS:** Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X *[Signature]*

DATE SIGNED *3-19-07* TIME SIGNED *0220*  A.M.  P.M.

REMIT PAYMENT TO:

SWIFT SERVICES, INC.  
P.O. BOX 466  
NESS CITY, KS 67560  
785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE		
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				PAGE TOTAL 1	6587.50
WE UNDERSTOOD AND MET YOUR NEEDS?				page 2	5478.10
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				subtotal	12025.60
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				Clark TAX 5.3%	501.22
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	12,526.82
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					



PO Box 466  
Ness City, KS 67560  
Off: 785-798-2300

TICKET CONTINUATION

TICKET No. 11462

CUSTOMER: American Warrior Trac. WELL: Esplan Farms CD&E, 419 DATE: 3-18-07 PAGE 2 OF 2

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			TIME	DESCRIPTION	QTY.		UNIT PRICE		AMOUNT		
		LOC	ACCT	DF			QTY.	UM	QTY.	UM	QTY.	UM	
330		2				8MD Cement	150	SKS	14 <sup>00</sup>		2100	00	
276		2				Flocle	38	#	1 <sup>25</sup>		47	50	
285		2				CFR-1	70	#	4 <sup>00</sup>		280	00	
287		2				Gas Step	300	#	7 <sup>00</sup>		2100	00	
290		2				Dein	1	gal	32 <sup>00</sup>		32	00	
RECEIVED KANSAS CORPORATION COMMISSION  MAY 17 2007  CONSERVATION DIVISION WICHITA, KS													
581		2				SERVICE CHARGE	150	SKS		1 <sup>10</sup>	165	00	
583		2				MILEAGE CHARGE				1 <sup>00</sup>	753	60	
										TOTAL WEIGHT		15072	
										LOADED MILES		100	
										CUBIC FEET		1	
										TON MILES		753,60	

CONTINUATION TOTAL 5478.10

**JOB LOG**

**SWIFT Services, Inc.**

DATE 3-18-07 PAGE NO. 1

CUSTOMER American Warrior Inc WELL NO. # CDFE 479 LEASE Expland Farms JOB TYPE Cement Logging TICKET NO. 11462

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	19:30							on loc w/FE
								5 1/2" x 15.5" x 5364 x 19'58"
								centralizers 1, 3, 7, 9, 11, 12, 15
								Basket 1, 9
	21:00							start F.F.
	0025							Break Circulation
	0030						1200	Drop Ball & set Plug Shoe
	0110	2	3/2					Plug RH & MH 15 sks + 10 sks
	0120	4	0				200	start PreFlush <sup>3 bbl w/FE</sup> <sub>750 gal Flocheck</sub>
	0127	5	28/0				250	start Cement <sup>135 sks SMD @ 12.5"</sup>
	0137		46					End Cement
								wash PL
								Drop Plug
	0140	6.5	0				200	start Displacement
	0156	4	95				250	catch Cement
	0203		127				700/200	land Plug
								Release Pressure
								Floatcheck

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 17 2007

CONSERVATION DIVISION  
WICHITA, KS

Thank you  
Nick, Josh & Ryan



CHARGE TO: *American Water Trac*  
 ADDRESS:  
 CITY, STATE, ZIP CODE:

TICKET  
 No 11473

PAGE: 1 OF 1

SERVICE LOCATIONS 1. <i>Hay 2, Ks</i> 2. <i>Ness City, Ks</i>	WELL/PROJECT NO. <i>4-19</i>	LEASE <i>Esplanad Farms CD&amp;E</i>	COUNTY/PARISH <i>Clack</i>	STATE <i>Ks</i>	CITY	DATE <i>4-2-07</i>	OWNER <i>Same</i>
TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR <i>Southwest Well Service</i>	RIG NAME/NO.	SHIPPED VIA <i>PT Location</i>	DELIVERED TO	ORDER NO.		
WELL TYPE <i>Gas</i>	WELL CATEGORY <i>Development</i>	JOB PURPOSE <i>PTA</i>	WELL PERMIT NO.	WELL LOCATION			
REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UNIT PRICE		AMOUNT
		LOC	ACCT	DF		QTY.	UM	QTY.	UM	
575		1			MILEAGE #163	160	mi	4	cc	480
576P		1			Pump Charge (PTA)	1	hr	800	cc	800
580		1			Add. hours	3	hrs	150	cc	450
328		2			Swift Light 60% Repair 6% gel	160	cks	9	cc	1520
274	RECEIVED KANSAS CORPORATION COMMISSION MAY 17 2007 CONSERVATION DIVISION WICHITA, KS	2			Acetate gel	15	shc	21	cc	315
581		2			Cement Service Charge	175	cks	1	cc	192
583		2			Drayage	759	34 TAM	1	cc	759

**LEGAL TERMS:** Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS  
*By Nick Kube*

X *Joe Smith*  
 DATE SIGNED *4-2-07* TIME SIGNED *1600*  A.M.  P.M.

REMIT PAYMENT TO:  
 SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	4436	54
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?						
WE UNDERSTOOD AND MET YOUR NEEDS?						
OUR SERVICE WAS PERFORMED WITHOUT DELAY?						
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				Clark TAX 5.3%	97	26
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	4534	10
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND						

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR *W. A. Hines* APPROVAL

Thank You!

**JOB LOG**

**SWIFT Services, Inc.**

DATE 4-2-07 PAGE NO. 1

CUSTOMER American Water Inc WELL NO. 4-19 LEASE Fidelity Farms, C.O.F.E. JOB TYPE PTA TICKET NO. 11473

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0945							caliber set up to 135'
								5.5" x 5364
								1st Plug @ 1360'
	1355	4	0			50		start gel 15 sks
		4	50/0			50		start cement 50 sks 6% Pac 6% gel
		4	15/0			50		End cement/Start water
	1414		3					Plug balanced
								2nd Plug @ 780'
	1455	4	0			50		start water
		4	5/0			50		start cement 50 sks 6% Pac 6% gel
	1500	4	15/0			5		start water
			3					End balanced
								3rd Plug @ 300'
	1525	4	0			50		start water
		4	5/0			50		start cement 100 sks 6% Pac 6% gel
		4	12/0			50		start water
	1536		1					Balanced
								11th Plug @ 40'
	1550		0					start water
			3/0					start cement 20 sks 6% Pac 6% gel
			15					End
								Top off RR
	1555		3					Top off RR

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 17 2007

CONSERVATION DIVISION  
WICHITA, KS

Thank you

Nick Tish & Sons

# ALLIED CEMENTING CO., INC.

24326

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Medicine Lodge, KS

DATE <u>04 MAR 07</u>	SEC. <u>19</u>	TWP. <u>30s</u>	RANGE <u>23w</u>	CALLED OUT <u>6:30pm</u>	ON LOCATION <u>9:30pm</u>	JOB START <u>2:15 AM</u>	JOB FINISH <u>3:15 AM</u>
LEASE <u>Esplund</u>	WELL # <u>4-19</u>	LOCATION <u>Bloom, Ks, 6 1/4 S, w/into</u>			COUNTY <u>Clark</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Murfin #22

TYPE OF JOB Surface

HOLE SIZE 12 1/4 T.D. 709

CASING SIZE 8 5/8 DEPTH 709

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 800 MINIMUM -

MEAS. LINE \_\_\_\_\_ SHOE JOINT 35.25

CEMENT LEFT IN CSG. 35

PERFS. \_\_\_\_\_

DISPLACEMENT 43 Bbls Fresh H<sub>2</sub>O

EQUIPMENT \_\_\_\_\_

OWNER Amer. Warrior

CEMENT

AMOUNT ORDERED 225sx65:35:6+3%cc + 1/4 # Flocal AND 100sx "A" + 3%cc + 2%gel

COMMON	<u>100 A</u>	@	<u>10.65</u>	<u>1065.00</u>
POZMIX		@		
GEL	<u>2</u>	@	<u>16.65</u>	<u>33.30</u>
CHLORIDE	<u>11</u>	@	<u>46.60</u>	<u>512.60</u>
ASC		@		
	<u>ALW 225</u>	@	<u>9.95</u>	<u>2238.75</u>
	<u>F10 seal 56<sup>th</sup></u>	@	<u>2.00</u>	<u>112.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>352</u>	@	<u>1.90</u>	<u>668.80</u>
MILEAGE	<u>75 X 352 X .09</u>			<u>2376.00</u>
				TOTAL <u>7006.45</u>

PUMP TRUCK CEMENTER D. FELLO

# 414 HELPER Lushenbery

BULK TRUCK

# 363 DRIVER R. Heffington

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

Pipe on Btm, Break Circ, Pump PreFlush, Mix 225sx litewieg up, Mix 100sx tail Cement, Stop Pump, Release Plug, Start Disp, Wash up on Plug, See Steady increase in Lift PSI, Slow Rate Bump Plug at 43 Bbls Fresh H<sub>2</sub>O Pipe total, Release PSI, Float Did Hold Cement Did. Circ.

SERVICE

DEPTH OF JOB 709

PUMP TRUCK CHARGE 0-300' 815.00

EXTRA FOOTAGE 409' @ .65 265.85

MILEAGE 75 @ 6.00 450.00

MANIFOLD headrental @ 100.00 100.00

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 17 2007

TOTAL 1630.85

CONSERVATION DIVISION  
WICHITA, KS

PLUG & FLOAT EQUIPMENT

1-TRP	@	<u>100.00</u>	<u>100.00</u>
1-AFU insert	@	<u>325.00</u>	<u>325.00</u>
1- Basket	@	<u>180.00</u>	<u>180.00</u>
2- centralizers	@	<u>55.00</u>	<u>110.00</u>
ANY APPLICABLE TAX @ _____			
WILL BE CHARGED UPON INVOICING			TOTAL <u>715.00</u>

TAX \_\_\_\_\_

TOTAL CHARGE ~~715.00~~

DISCOUNT ~~\_\_\_\_\_~~ IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

8 5/8"

SIGNATURE Kelly Wilson

PRINTED NAME \_\_\_\_\_