

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-109-20360-00-00

API NUMBER 15-109-20,360-00-00

LEASE NAME B. B. Stoller

WELL NUMBER 1

SPOT LOCATION NE NW

SEC. 35 TWP. 11 SRGE 36W (E) or (W)

COUNTY Logan

Date Well Completed 11-26-84

Plugging Commenced 11-26-84

Plugging Completed 11-26-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300, Wichita, KS 67202

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? KCC, Hays, Ks.

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 5010'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8-5/8"	343'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st plug @ 2800' w/ 20 sx;
2nd plug @ 1650' w/ 10 sx;
3rd plug @ 375' w/ 40 sx;
4th plug @ 40' w/ 10 sx;
10 sx in rat hole; 10 sx in mouse hole.

RECEIVED
STATE CORPORATION COMMISSION
1-26-1985
JAN 28 1985
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033
Address 250 N. Water, Suite 300, Wichita, KS 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack E. Goss (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct to the best of my knowledge.

(Signature) [Signature]
Jack E. Goss, Agent for Operator
(Address) 250 N. Water, Suite 300
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 17 day of January, 19 85

[Signature]
Eleanor Hall Notary Public



My Commission Expires: 4-25-87

WELL LOG

COMPANY Murfin Drilling Company
 250 N. Water, Suite 300
 Wichita, KS 67202

FARM B. B. STOLLER **NO.** 1


SEC. 35 **T.** 11S **R.** 36W
LOC. NE NW

RIG. NO. 24

TOTAL DEPTH 5010'

COMM. 11-17-84 **COMP.** 11-26-84

COUNTY Logan **KANSAS**



CONTRACTOR Murfin Drilling Company
 250 N. Water, Suite 300
 Wichita, KS 67202

CASING

20	10	
15	8	4 5/8" csg set @ 343' w/250 sx 60-40
12	6	Pozmix, 3% CC.
13	5	

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & Sand	205'
Shale	1350'
Sand & Shale	2789'
Anhydrite	2816'
Shale & Shells	2970'
Shale	3295'
Sand & Shale	3520'
Shale & Lime	(RTD) 5010'

RECORDED
 STATE CORPORATION COMMISSION
 1-28-1985
 JAN 28 1985
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Sedgwick } ss:

I, Jack E. Goss of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the B. B. Stoller #1 well.



Jack E. Goss
 Jack E. Goss, Agent for Operator

Subscribed and sworn to before me this 17th day of January 19 85

My Commission Expires 4-25-87

Eleanor Hall
 Eleanor Hall NOTARY PUBLIC