

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Petroleum Technologies, Inc.
Address: 801 W. 47th Suite 412 Kansas City, Mo. 64112
Phone: (816) 531-6904 Operator License #: 8653

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)
by: Patrick Staab (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 009-04469-00-00
Lease Name: Kramp
Well Number: 2
Spot Location (QQQQ): _____ - SW - NE - NE
4290 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 7 Twp. 19 S. R. 11 East West
County: Barton
Date Well Completed: _____
Plugging Commenced: 5-11-09
Plugging Completed: 5-13-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"		None
				5-1/2"	3364'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated well @1300', 500' & 300'. Ran 2-7/8" tubing to 3100', pumped 12 sxs. gel & 60 sxs. cement, pulled tubing up to 1350', pumped 75 sxs. cement w/150# hulls, pulled up to 600', pumped 175 sxs. cement. Tied onto annulus, pumped 5 sxs. cement, pressured up to 300#, shut in. Top of cement @390', ran tubing to 390' and circulated 110 sxs. cement to surface. Topped off with 10 sxs. Used 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: _____
State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 19th day of May, 20 09

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 21 2009

KCC WICHITA

[Handwritten initials]