

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: Landowner
Name: Mull Creek Ranch/Kim Leeper
Address 1: 2852 Highway 160
Address 2: _____
City: Medicine Lodge State: KS Zip: 67104 + _____
Contact Person: Kim Leeper
Phone: (620) 248-3265
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: ~~CWD Permit # E-22141~~
 ENHR Permit #: E-22141 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet):
_____ Depth to Top: 4725 Bottom: 4735 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 7 00-21508-00-01
Spot Description: _____
NE NE SW Sec. 30 Twp. 32 S. R. 15 East West
2,316 Feet from North / South Line of Section
2,970 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barber
Lease Name: Brass Well #: 4
Date Well Completed: 10/25/1982
The plugging proposal was approved on: 3/24/2009 (Date)
by: Steve Pfeifer (KCC District Agent's Name)
Plugging Commenced: 4/10/2009
Plugging Completed: 4/15/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		53'	16"	53'	None
		416'	8 5/8	416'	None
		4793'	4 1/2	4793'	2300'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set cast iron bridge plug 4670', 2 sacks cement with dump bailer, pull casing, 15 sacks gel, 50 sacks 60/40 POZ 4% gel, 100 hulls at 760', 50 sacks at 440', 20 sacks at 60'
4/23/2009 - measure in 8' from surface, 2 sacks cement

Plugging Contractor License #: 5105 Name: Clarke Corporation
Address 1: P.O. Box 187 Address 2: 107 W. Fowler
City: Medicine Lodge State: KS Zip: 67104 + _____
Phone: (620) 886-5665
Name of Party Responsible for Plugging Fees: Mule Creek Ranch / Kim Leeper Landowner KCCPTA
State of Kansas County, Barber, ss.
Mark Morgenstern Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above described well, and that the same are true and correct, so help me God.

Signature: Mark Morgenstern

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MAY 20 2009
RECEIVED

Per KCCPTA