

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior, Inc.  
Address: P.O. Box 399  
Phone: (785) 398-2270 Operator License #: 4058  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 05/14/2009 (Date)  
by: Mike Maier (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Chase Depth to Top: 2171' Bottom: 2234' T.D. 2450'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-135-24071-0000  
Lease Name: Young  
Well Number: 1-13  
Spot Location (QQQQ): - C - NE -  
1320 Feet from  North /  South Section Line  
1320 Feet from  East /  West Section Line  
Sec. 13 Twp. 18 S. R. 21  East  West  
County: Ness  
Date Well Completed: 08/06/1999  
Plugging Commenced: 05/14/2009  
Plugging Completed: 05/14/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Chase	Gas	2176'	2234'	8 5/8"	221'	None
				4 1/2"	2446'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Swift Services mixed 150 sacks of 60/40 poz, 4% gel with 1/4# flocele with 200# of hulls and pumped down 4 1/2" casing.  
Swift Services mixed 30 sacks of 60/40 poz, 4% gel with 1/4# flocele pumped in down 8 5/8" braden head, pressure 500 PSI.  
Swift Services returned after 2 hours and mixed 30 sacks of 60/40 poz, 4% gel with 1/4# flocele and topped off 4 1/2" casing,  
Job complete. Well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382  
Address: N Highway 283, Ness City, KS 67560

RECEIVED  
MAY 19 2009

Name of Party Responsible for Plugging Fees: American Warrior, Inc.  
State of Kansas County, Ness, ss.

KCC WICHITA

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 210 W Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 18th day of May, 20 09

[Signature]  
Notary Public

My Commission Expires 8-15-12  
NOTARY PUBLIC - State of Kansas  
DENISE CORSAIR  
8-15-12

Mail to: KCC - Conservation Division, 130 S. Market - Room 2000 - Wichita, Kansas 67202

[Handwritten initials]