

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P.O. Box 399
Phone: (785) 398-2270 Operator License #: 4058
Type of Well: Oil/Gas KCC per permit Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 05/14/2009 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chase Depth to Top: 2180' Bottom: 2240' T.D.: 2284'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-24080-0000
Lease Name: Young
Well Number: 1-12
90' S of C
Spot Location (QQQQ): NW - SW - SE - _____
800 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 12 Twp. 18 S. R. 21 East West
County: Ness
Date Well Completed: 09/12/1999
Plugging Commenced: 05/14/2009
Plugging Completed: 05/14/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Chase	Gas	2174'	2284'	8 5/8"	227	None
				4 1/2"	2283'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Swift Services mixed 150 sacks of 60/40 poz, 4% gel with 1/4# flocele with 200# of hulls and pumped down 4 1/2" casing.
Swift Services mixed 25 sacks of 60/40 poz, 4% gel with 1/4# flocele pumped in down 8 5/8" braden head, pressure 500 PSI.
Swift Services returned after 2 hours and mixed 25 sacks of 60/40 poz, 4% gel with 1/4# flocele and topped off 4 1/2" casing,
Job complete. Well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
Address: N Highway 283, Ness City, KS 67560
Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Ness, ss.

RECEIVED
MAY 19 2009
KCC WICHITA

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) _____
(Address) 210 W Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 18th day of May 20 09
Denise Corsair My Commission Expires 8-15-12
Notary Public State of Kansas



Mail to: KCC - Conservation Division, 130 S. Market - Room 2092, Wichita, Kansas 67202