

15-051-01542-0000

BOWLBY "A" NO. 1 WELL

LOCATION:

^{RTKCC}
 Cen. S $\frac{1}{2}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ Sec. 1-115-16W
 Ellis County, Kansas

SPUDED: 6-23-64

COMPLETED: 7-3-64

OPERATOR & CONTRACTOR:

Birmingham-Bartlett Drilling Co.
 300 Kaufman Building
 Wichita, Kansas

ELEVATION: 1887 GL
 1889 DF
 1892 RB

SURFACE CASING:

8-5/8" surface casing cemented at
 166' with 135 sacks cement.

TOPS RB

OIL STRING:

5-1/2" OD 14# 8 Rd J-55 R-2
 Smls. Casing set at 3464' with 165 sacks
 cement and 2 sacks Jel.

Anhydrite	1063	+ 829
Topeka	2788	- 896
Heebner	3030	-1138
Toronto	3053	-1161
Lansing	3079	-1187
Conglomerate	3408	-1516
Arbuckle	3457	-1565
RTD	3555	-1663

LOG

0 -	167	Clay & Shale
	260	Shale & Shells
	410	Sand
	495	Shale & Red Bed
	750	Shale & Sand
	1063	Red Bed
	1098	Anhydrite
	1150	Shale
	1680	Shale & Shells
	2275	Lime & Shale
	2650	Shale & Shells
	2855	Shale & Lime
	3020	Lime
	3062	Shale & Lime
	3162	Lime
	3190	Lime & Shale
	3315	Lime
	3330	Shale & Lime
	3410	Lime
	3466	Lime & Shale
	3555	Lime
	3555	Rotary Total Depth

DRILL STEM TESTS:

#1: 3028-62. Open 20". Rec. 5' mud
 BHP 887#-660# FP 28#-31#
 #2: 3062-90. Op 25". Rec. 5' mud.
 BHP 102#-43: FP 23#-34#
 #3: 3097-3124 Op 1 hr. Rec. 1200' gas,
 240' mud-cut oi. 300' oilcut
 mud 50% oil; 120' oilcut water 70%
 water, 180' wtr. slightly oilcut
 #4: BHP 589-581: FP 62#-353#
 #4: 3144-64. Op 40" Rec. 10' sl. oil-
 cut mud. BHP 70#-47#, FP 23#-31#
 #5: 3174-3202. Op 1 hr. Rec. 60' muddy
 SW. BHP 463#-432#, FP 39#-54#
 #6: DST 3277-3330' Op 20" Rec. 5' mud
 BHP 216#-67#, FP 0.

DRILLING-IN

Drilled plug, tested 40 BWPH. Set
 plug 3415' perforated 3107'-13' with
 24 shots, 500 gal. acid. Well completed
 for potential of 20 BOPD
 BIRMINGHAM-BARTLETT DRILLING CO.

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the Bowlby "A" No. 1 Well, as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery
 Richard Hindery, Partner

Subscribed and sworn to before me
 this 6th day of July, 1964.

Vivian F. Yinger
 Vivian F. Yinger, Notary Public
 My Commission Expires: November 29, 1966.

Well started producing all water so production
 abandoned on April 24, 1973 and well then
 converted to Salt Water Disposal Well.

