


Krueger Unit Tr. 9 well 2

COPY

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
Wichita, KansasCompany. SKELLY OIL COMPANY
Farm. R. C. Howlby No. 2SEC. 2 T. 11 R. 16W
NW 1/4 NE
990' FSL 330' FWL NE/4Total Depth. 3620 P. R. 3587
Comm. 9-15-49 Camp. 10-16-49
Shot or Traced. 5750 gals.
Contractor. Claude Wentworth Drig. Co.
Issued. 12-3-49

County. Ellis

KANSAS



CASING:
 13" set @ 75' w/100 sx.
 8" set @ 1225' w/525 sx.
 5" set @ 3614' w/300 sx.

Elevation. _____

Production. 864 Bbls.

Figures indicate Bottom of Formations.

Surf. soil & sd. rock	55
Sand	67
Shale & shells	97
Shale	700
Shale & shells	990
Red b. d. & shale	1218
Anhydrite	1255
White sand	1265
Shale & shells	1525
Salt & shale	1670
Shale & shells	1880
Lime	1940
Shale & lime	2185
Lime	2225
Lime & shale	2290
Lime	2395
Lime & shale	2805
Lime	2870
Shale	2970
Shale & lime	2975
Lime	3161
Lime & shale	3211
Lime	3550
Conglomerate	3578
Lim.	3595
Dolomite	3620

Total Depth

FORMATION TOPS:

Topeka ls.	2975
Huebner sh.	3186
Toronto ls.	3209
Lansing ls.	3231
Congl.	3550
Simpson sh.	3587
Arbuckle ls.	3595

Fair to good saturation 2975-85
 Fair oil saturation 3211-15
 " " " 3231-3445