

Inorn Drilling Company etal, Owner - Aiken #2  
SW NE SE section 4, Township 10, Range 17N,  
Rocks County, Kansas

Elevation: 2083 KB

Figures indicate bottom of formation

PIPE RECORD:

8-5/8" set at 190'  
5-1/2" set at 3560'

TOPS: RBM

Heobner 3191  
Toronto 3210  
Base Oread 3223  
Lansing 3230  
Base K.C. 3467  
Arbuckle 3500

0 to 60 clay & posé rock  
95 shale & sand  
630 shale & shells  
655 sand  
670 shale & shells  
690 sand  
760 shale & shells  
1030 shale & sand  
1150 shale & shells  
1190 Red bed  
1316 shale & shells  
1350 Anhydrite  
1665 shale & shells  
1835 salt  
2110 shale & shells  
3105 lime & shale  
3500 lime  
3560 Arbuckle  
3560 Total Rotary Depth

Rotary Commenced 7-14-53  
Completed 7-23-53

CABLE TOOLS WORK

Cable Tools Commenced 7-30-53-----Completed 8-1-53

Moved in cable tools and cleaned out to 3551' KB. Ran radioactivity log.  
Perforated from 3524-28 with 24 shots. Acidized with 500 gallons acid. Pumped  
approximately 20 barrels oil per day with 95% water.

Cable Tools Commenced 9-17-53-----Completed 10-15-53

Moved cable tools back in. Squeezed perforations 3524-28 with 45 sacks cement.  
Perforated from 3516-20 with 24 shots. Acidized with 500 gallons acid. Swabbed hole  
full of water. Squeezed above perforations with 134 sacks. Reperforated 3516-20.  
Acidized with 500 gallons acid. Swabbed all water. Squeezed above perforations then  
perforated from 3525-27. Acidized with 500 gallons acid, and swabbed all water.  
Squeezed above perforations. Plugged back to K.C. Perforated from 3433-37 with 16  
shots--also 3455-64 with 32 shots. Acidized with 5,000 gallons acid. Set temporary  
plug at 3426'. Perforated from 3400-04 with 12 shots. Perforated 3416-20 with 12 shots.  
Acidized with 2,000 gallons. Drove bridge plug from 3426-90. Put on pump. Completed as  
minimum well in K.C.

STATE OF KANSAS )  
COUNTY OF BARTON ) SS

I, Warren O. Johnson, Employee of the Owner of the above-described well, being first  
duly sworn on oath, declare: That I have knowledge of the facts, statements and matters  
herein contained pertaining to the log of the above-described well as filed and that  
the same are true and correct.

*Warren O. Johnson*

Subscribed and Sworn to before me this 16th day of December, 1953.

My commission expires Feb. 10, 1955.

*Sergeant A. Meyer*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1970  
CONSERVATION DIVISION  
Wichita, Kansas