

WELL LOG BUREAU—KANSAS GEOLOGICAL SURVEY  
508 East Murdock, Wichita, Kansas

15-163-00424-0000


Company- BAY PETROLEUM  
Farm- Kompe "A" No. 6

SEC. 31 T. 10 R. 17  
SW NE SW

Total Depth. 3619  
Comm. 8-6-52 Camp. 9-30-52

County Rooks  
KANSAS

Shot or Treated.  
Contractor: Pickrell Drlg.  
Issued. 11-1-52



CASING:

Elevation. 2063

8 5/8" 162' cem. w/125 sx. circ.  
5 1/2" 3615 cem. w/250 sx.

Production. Phys. pot. 19 BO  
/ 94% wtr.

Figures Indicate Bottom of Formations.

Meas. from top of rotary bushing

surface	162
shale	450
sand & shale	800
red bed & shale	1385
Anhyd.	1395
Anhyd.	1415
shale & salt	1695
shale & shells	1900
lime & shale	1950
lime & shale brks	2120
shale & lime	2250
lime & shale	2350
lime & shale brks	2425
lime & shale	2780
shale & lime	2920
shale & shells	3020
lime	3603
lime & shale	3616
lime & shale	3619
Total Depth	

Tops:	
Topeka	3017
Heebner	3240
Lansing	3282
Congl.	3531
Simpson	3593
Arbuckle	3612

RECEIVED  
STATE CORPORATION COMMISSION

MAR 10 1978

CONSERVATION DIVISION  
Wichita, Kansas

SLM at 3500' OK

D.S.T. 3595-3601 D.F. op. 1 hr. SI 15"  
Rec. 65' muddy salt wtr. 530# BHP DC & CO  
to T.D. 3614 HPW DD 2', no change D.D. 2' no  
change. Plastic plug to shut off wtr.  
Drilled plastic to 3618 2 1/2 bbl. oil /  
SSOPH. DD 1' to 3619. FU 2500 w/wtr.  
Plastic plug. Drilled to 3614 D.F. Perf.  
15 / 3610-12 1/2, Test 18 GWPH / 18 SOPH  
500 acid swb. 3. BO / 25 BWP