



15-109-20017-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-12-1972
DEC 12 1972
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Dale Bucheister of John O. Farmer has this

date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Webber Well No. 1

Location: CNW-NE Sec. 14 Twp. 11 Rge. (E)(W) 32

County: Logan Total Depth 4687' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 1500'.

Circulate hole with heavy mud. Pull DP to 1725' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent