



15-109-20008-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
11-23-1970
NOV 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Coldwater of Alpine Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Coldwater guarantees payment of the plugging fee.

Operator's full Name: Alpine Drilling Company, Incorporated,

Complete Address: 800 Bitting Building, Wichita, Kansas.

Lease Name: Nollette Well No. 1

Location: CSE-SW Sec. 7 Twp. 11 Rge. (E)(W) 33

County: Logan Total Depth 4800' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Coldwater was instructed to plug the well as follows:

284'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1375'.

Circulate hole with heavy mud. Pull DP to 1600' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent