



15-109-20003-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Erlich of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Erlich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Yeoman Well No. 1

Location: CSW-SW Sec. 7 Twp. 11 Rge. (E)(W) 36

County: Logan Total Depth 4120 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Erlich was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated.

Circulate hole with heavy mud. Pull DP to 1600' and displace 100 Sx. cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent