

3 023148

15-207-02005-00-00

4-26-07

To:

API NUMBER 20070029-038

STATE CORPORATION COMMISSION

SW SE,SW,NE 1/4 Sec/Twp/Rge S.21-T.26S.-R.16E.

Wichita State Office Bldg. - PLUGGING SECTION

2684 feet from south section line

130 S. Market, Room 2078

1782 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# Rose East-Bishop 6  
BISHOP NO. 6Operator License # 100 101County WOODSONOperator: STATE OF KANSASWell Total Depth 1100' feetName & FEE FUND PLUGGINGProduction Pipe: 2" Size Feet 1100'

Address

Surface Casing: 6" Size Feet 40'AB oil well        Gas Well        SWD Well/ Input Well X D & A       

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 9:00A.M. Day:        2 Month:        3 2007Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CEMENT LINED 2" TO APPROXIMATELY 1100' THATHAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATEAS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2"CASING.Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All        Part X TECHNICIAN NoneOperations Completed: Hour: 4:00P.M. Day:        2 Month:        3 2007Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 1040'. CEMENTWAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING ATSURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 6" ANNULUSTO 675'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE2" AND 6" ANNULUS AT SURFCD. THE 1" PIPE WAS REMOVED. DISPLACEMENT WASFILLED FROM SURFACE. 325 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: (SPOT LOCTION ESTABLISHED BY GPS AS BIS 06) Control #20070029-038  
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

RECEIVED  
KANSAS CORPORATION COMMISSIONClayton P. Titel  
TECHNICIAN

APR 26 2007

CONSERVATION DIVISION  
WICHITA, KS

33749

PVS