

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133-01663-00-00
SW NE NW Sec/Twp/Rge 33-28-21E
4123 (GPS) feet from south section line
3815 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Dent/Vanleeuwen Lease Project
Address _____
AB oil well _____ Gas Well _____

Lease/Well# Dent GPS #17
County Neosho
Well Total Depth 450 (est) feet
Production Pipe: 2 Size Feet 450 (est)
Surface Casing: 10 Size Feet NA
SWD Well/ Input Well E-08930.3 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749
Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 8 Month: 12 2008

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ None XXXXXX

TECHNICIAN
RECEIVED
KANSAS CORPORATION COMMISSION
DEC 29 2008
CONSERVATION DIVISION
WICHITA, KS

Operations Completed: Hour: _____ Day: 8 Month: 12 2008

Actual Plugging Report: 340' of the 1" pipe with packer, was removed. The well was then perforated at 250' and 150'. A 1" cement string was lowered to 400' and the well pumped full of cement from btm to top thru this cement string. A total of 27 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20080018-017
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: Alan M. Dunning
TECHNICIAN