

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-121- 01806-00-00  
SENWSW Sec/Twp/Rge 25-16S-21E  
1910 feet from south section line  
4196 feet from east section line

Ø

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# DUNN ~~SPC#19~~ #19

Operator: STATE OF KANSAS

County MIAMI

Name & FEE FUND

Well Total Depth 650 EST. feet

Address \_\_\_\_\_

Production Pipe: 2 Size Feet 650 EST.

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_ SWD Well/ Input Well E 1521 D & A \_\_\_\_\_

Surface Casing: 10 Size Feet 20 EST.

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: K-W OIL WELL SERVICES, INC. Lic. # 3097

Address: 19450 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 13 Month: NOV 2006

Plugging proposal received from: SAM KEPLEY

Company Name: KW OIL WELL SERVICES, INC. Phone: 620-496-7173

Were: PLUG WELL WITH PORTLAND CEMENT, TD TO SURFACE.

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All \_\_\_\_\_ X \_\_\_\_\_ Part \_\_\_\_\_  
TECHNICIAN  
None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 15 Month: NOV 2006

Actual Plugging Report: PULL 3/4" LOOSE AND PULL OUT WITH PACKER. RUN 1" TO 650 FT  
INSIDE 2". RUN 1" TO 325 FT OUTSIDE 2". WASH TO 400 FT OUTSIDE 2". PUMP PORTLAND CEMENT  
FROM TD TO SURFACE INSIDE AND OUTSIDE 2". PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF  
117 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL # 20060060-037 GPS# DUN19 CONTRACT # 09569  
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: FRANK GUILFOYLE  
TECHNICIAN

RECEIVED  
NOV 27 2006  
KCC WICHITA

PS