

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-121- 01789 -00-00
SWSWNW Sec/Twp/Rge 25-16S-21E
2948 feet from south section line
4654 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# AC PFLUG ~~GPS# 30~~ #30Operator: STATE OF KANSASCounty FRANKLINName & FEE FUNDWell Total Depth 650 EST. feet

Address

Production Pipe: 2 Size Feet 650 EST.AB oil well X Gas Well SWD Well/ Input Well Surface Casing: 8 Size Feet 20 EST.Other well as hereinafter indicated: Plugging Contractor: K-W OIL WELL SERVICES, INC. Lic. # 3097Address: 19450 FORD ROAD CHANUTE, KS. 66720Company to plug at: Hour: Day: 6 Month: OCT 2006Plugging proposal received from: SAM KEPLEYCompany Name: KW OIL WELL SERVICES, INC. Phone: 620-496-7173Were: PLUG WELL WITH PORTLAND CEMENT, TD TO SURFACE.

Plugging Proposal Received by:

FRANK GUILFOYLEPlugging attended by Agent: All Part TECHNICIAN
X None Operations Completed: Hour: Day: 11 Month: OCT 2006Actual Plugging Report: CLEAR TREES AROUND LOCATION. RUN 1" INSIDE 2" TO 600 FT.RUN 1" OUTSIDE OF 2" TO 325 FT. WASH 1" TO 450 FT OUTSIDE 2". PUMP PORTLAND CEMENTUNTIL RAN OUT. PULL PIPE. RUN 1" BACK NEXT DAY AND TAG CEMENT INSIDE AND OUTSIDE 2".FINISH FILLING UP. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 130 SACKS OF CEMENT.WELL PLUGGEDRemarks: CONTROL # 20060060-016 GPS# ACP 30 CONTRACT # 09569(If additional description is necessary, use BACK of this form.)I DID/PART observe this plugging.

Signed:

FRANK GUILFOYLE

TECHNICIAN

RECEIVED

NOV 06 2006

KCC WICHITA