

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-059-19996-00-00  
NWNWNE Sec/Twp/Rge 10-16S-21E  
4698 feet from south section line  
2227 feet from east section line



TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: STATE OF KANSAS  
Name & FEE FUND  
Address \_\_\_\_\_

Lease/Well# EGDORSEY 2-F ~~GPS EGD05~~  
County FRANKLIN  
Well Total Depth 650 EST. feet  
Production Pipe: 2 Size Feet 650 EST  
Surface Casing: 8 Size Feet 20 EST.

AB oil well  Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: K-W OIL WELL SERVICES, INC. Lic. # 3097

Address: 19450 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 21 Month: SEPT 2006

Plugging proposal received from: SAM KEPLEY

Company Name: K-W OILWELL SERVICES, INC. Phone: 620-496-7173

Were: PLUG WELL WITH PORTLAND CEMENT TD TO SURFACE.

**RECEIVED**  
**SEP 20 2006**

**KCC WICHITA**

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All \_\_\_\_\_ Part X None \_\_\_\_\_  
TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ 22 Month: SEPT 2006

Actual Plugging Report: RUN 1" TO 650 FT INSIDE 2". RUN 1" TO 300 FT OUTSIDE 2". WASH

1" TO 525 FT OUTSIDE 2". PUMP PORTLAND CEMENT TO SURFACE INSIDE 2" AND OUTSIDE 2".

PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 195 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL NO. 20060050-027 GPS # EGD05 CONTRACT NO. 09378

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: FRANK GUILFOYLE  
TECHNICIAN