

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-133- 01654-00-00  
SE NE NW Sec/Twp/Rge 33-28-21E  
4123 (GPS) feet from south section line  
2656 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Dent GPS #06

Operator: State Of Kansas Fee Fund

County Neosho

Name & Dent/Vanleeuwen Lease Project

Well Total Depth 450 (est) feet

Address \_\_\_\_\_

Production Pipe: NA Size Feet NA

AB oil well XXXXXX Gas Well \_\_\_\_\_

Surface Casing: 8 Size Feet NA

SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 24 Month: 11 2008

Plugging proposal received from: Mike Kepley

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 24 Month: 11 2008

Actual Plugging Report: A 1" pipe with a 6.5" swedge was lowered to 200' unobstructed. The swedge was removed and a 1" cement string lowered to 300' where the pipe hit solid. The well was then pumped full of cement from btm to top thru this cement string. A total of 97 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 11 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Control #20080018-006

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: Alan M. Dunning  
TECHNICIAN

*Handwritten initials*