

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-133-01657-00-00  
NW NW NE Sec/Twp/Rge 33-28-21E  
4681 (GPS) feet from south section line  
2636 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Dent GPS #09

Operator: State Of Kansas Fee Fund

County Neosho

Well Total Depth 825 feet

Name & Dent/Vanleeuwen Lease Project

Production Pipe: 4 Size Feet 825

Address \_\_\_\_\_

Surface Casing: 6 Size Feet NA

AB oil well XXXXXX Gas Well \_\_\_\_\_

SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 27 Month: 10 2008

Plugging proposal received from: Mike Kepley

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 27 Month: 10 2008

Actual Plugging Report: A 2.275" swedge on a 1" pipe was lowered to 825'. The swedge and the 1" pipe were removed. The well was then perforated at 400' and 200'. A 1" cement string was lowered to 825' and the well pumped full of cement from btm to top thru this cement string. A total of 91 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20080018-009  
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 10 2008

CONSERVATION DIVISION  
WICHITA, KS

Alan M. Dunning  
TECHNICIAN

*[Handwritten signature]*