

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: MORRIS ENERGY  
Address: PO BOX 305 WEIR, KS 66781-0305  
Phone: (417) 438-7921 Operator License #: 33495  
Type of Well: ENHR Docket #: E-17959  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 2-9-09 (Date)  
by: JOHN ALMOND (KCC District Agent's Name)  
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No  
Producing Formation(s): List All (If needed attach another sheet)  
CATTLEMAN Depth to Top: 200 Bottom: 220 T.D. 225  
Depth to Top: Bottom: T.D.  
Depth to Top: Bottom: T.D.

API Number: 15 - (PRE-1967)  
Lease Name: SAMP  
Well Number: sam- 09 (6 W.I.)  
Spot Location (QQQQ): SW - SW - NE - NW  
4008 Feet from ☐ North / ☒ South Section Line  
3802 Feet from ☒ East / ☐ West Section Line  
Sec. 7 Twp. 31 S. R. 22 ☒ East ☐ West  
County: CRAWFORD  
Date Well Completed: N-A, NO RECORD  
Plugging Commenced: 2-9-09  
Plugging Completed: 2-9-09

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface Conductor & Production) |      |      |          |            |
|---------------------------|---------|--|------|------|----------|------------|
| Formation                 | Content | From   | To   | Size | Put In   | Pulled Out |
|                           |         | SURFACE  | 20'  | 6"   | IN-PLACE | NONE       |
|                           |         | SURFACE  | 200' | 2"   | IN-PLACE | NO         |
| CATTLEMAN                 | OIL     | 200'   | 220' |      |          |            |
|                           |         |  |      |      |          |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Washed down 1" steel tubing inside the 2" casing to TD. Pumped 8 sacks of Portland (mixed 6 gallons of water per sack) and circulated cement to surface. Pulled out 1" cementing string and topped off with cement. Installed valve and squeezed 4 sacks of cement to 400 PSI and shut-in. Twelve (12) sacks total. Backside of 2" casing was already cemented and is in good condition.

Name of Plugging Contractor: Morris Energy License #: 33495  
Address: PO Box 305 Weir, KS 66781

Name of Party Responsible for Plugging Fees: MORRIS ENERGY (Derek Morris)  
State of Kansas County, Crawford, ss.

Derek Morris, owner / operator

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]  
(Address) PO Box 305 WEIR, KS 66781

SUBSCRIBED and SWORN TO before me this 31 day of March, 2009  
Patricia J. Tavernaro Commission Expires: 6-12-2010  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

APR 20 2009

KCC WICHITA

*[Handwritten initials]*