

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-063-21,338-00-00

LEASE NAME McDonald

WELL NUMBER 1

330 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 17 TWP. 11 SRGE. 31 ~~XXXX~~(W)

COUNTY Gove

Date Well Completed 8-27-90

Plugging Commenced 8-27-90

Plugging Completed 8-27-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petex, Inc.

ADDRESS 111 S. Glenstone - #1-104
Springfield, MO 65804

PHONE#(417) 887-6289 OPERATORS LICENSE NO. 8541

Character of Well D & A

~~XXXXXXXX, D&A, XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX~~

The plugging proposal was approved on 8-27-90 (date)

by Dale Balthazar (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom T.D. 4622'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Spotted 25 sx. cement @ 2530' thru drill pipe.

Spotted 100 sx. cement @ 1695' thru drill pipe.

Spotted 40 sx. cement @ 250' thru drill pipe.

Spotted 10 sx. cement @ 40' thru drill pipe. Spotted 15 sx. cement in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 1586, Great Bend, KS 67520

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petex, Inc.

SEP 4 1990

STATE OF Kansas COUNTY OF Sedgwick, ss.

Michael L. Considine (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Michael L. Considine
(Address) 401 E. Douglas - Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 90

My Commission Expires:

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Sept. 5, 1992

Notary Public



15-063-21338-00-00

WHITE

ANDELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Petex, Inc., 111 S. Glenstone - #1-104, Springfield, MO 65804

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name McDonald Well No. 1

Sec. 17 T. 11S R. 31W Spot SE SW SW

County Gove State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 210' with 140 sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4622'

Drilling Commenced 8-20-90 Drilling Completed 8-27-90

Formation	From	To	Tops
Cellar	0	7	Anhydrite 2501
Shale	7	2950	Kansas City 4100
Shale & Lime	2950	3600	Lansing 4185
Shale	3600	3910	Kansas City 4235
Shale & Lime	3910	4622	Ft. Scott - Cherokee 4430

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1990

CONSERVATION DIVISION
Wichita, Kansas