

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD #4
K.A.R.-82-3-117

15-147-30094-00-00

API NUMBER 10-21-65

LEASE NAME Stoneman

WELL NUMBER 6

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 20 TWP. 4 RGE. 18 KEXor(W)

COUNTY Phillips

Date Well Completed Sept. 1965

Plugging Commenced 9/1/88

Plugging Completed 9/1/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 North Woodlawn, Suite 201, Wichita, KS

PHONE#(316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/16/88 (date)

by Hays (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? no-filed with application

Producing Formation Kansas City Depth to Top 3184' Bottom 3264 T.D. 3350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	oil			8-5/8"	195'	0
				4-1/2"	3348'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran tubing to 2000'. Mixed 60' down tubing. Pulled to 1000' mixed cement until it circulated to top. Pulled tubing. Pumped 25 sx down casing. Pressured to 700 PSI. Shut in @ 400#. Pumped 15 sx down annulus. Pressured to 700#. Shut in at 500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address 400 N. Woodlawn, Suite 201, Wichita, Kansas 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

Steven P. O'Neill

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) *Steven P. O'Neill*

(Address) 400 N. Woodlawn, Wichita, KS 67208

SEP 20 1988

SUBSCRIBED AND SWORN TO before me this 16th day of Sept., 19 88

CONSERVATION DIVISION
Wichita, Kansas

Rebecca Wold
Notary Public

My Commission Expires: 12/21/91

