

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # _____ EXPIRATION DATE _____

OPERATOR Rains & Williamson Oil Co., Inc. API NO. 15-167-21,958-00-00

ADDRESS 435 Page Court, 220 W. Douglas COUNTY Russell

Wichita, Kansas 67202 FIELD _____

** CONTACT PERSON Juanita Green PROD. FORMATION _____

PHONE 265-9686

PURCHASER _____ LEASE John

ADDRESS _____ WELL NO. #1

WELL LOCATION SE SE SW

DRILLING Rains & Williamson Oil Co., Inc. 330 Ft. from S Line and ^{AWB} CC

CONTRACTOR ADDRESS 435 Page Court, 220 W. Douglas 2310 Ft. from W Line of

Wichita, Kansas 67202 the (Qtr.) SEC 11 TWP 12S RGE 14W.

PLUGGING Same

CONTRACTOR ADDRESS _____

WELL PLAT

(Office Use Only)

KCC

KGS

SWD/REP _____

PLG. _____

TOTAL DEPTH 3437' PBTD _____

SPUD DATE 7-26-82 DATE COMPLETED 8-1-82

ELEV: GR 1755 DF _____ KB 1760

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 247' DV Tool Used? _____

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry) Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

STATE RECEIVED
AUG 13 1982
08-13-82
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

Wilson Rains, President, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.


Wilson Rains
(Name)

Wilson Rains

SUBSCRIBED AND SWORN TO BEFORE ME this 11 day of August, 19 82.

Juanita M. Green
(NOTARY PUBLIC)
Juanita M. Green

19 82.
MY COMMISSION EXPIRES: 10-4-83



** The person who can be reached by phone regarding any questions concerning this information.

15-167-21958-00-00

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Rains & Williamson Oil Co. LEASE John #1 SEC. 11 TWP. 12SRGE. 14W
Inc.

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 2976-3020, 30 (30) 30 (30). Rec. 20' WM. FP's 50-50, 60-60. IBHP 644, FBHP 427. Temp. 100°.			<u>E. LOG TOPS</u>	
			Anhydrite	819 (+941)
DST #2 - 3131-3175, 30 (30) 30 (30). Rec. 60' MSW. FP's 60-60, 79-79. IBHP 998. Temp. 102°.			Topeka	2694 (-934)
			Heebner	2918 (-1158)
			Lansing	2970 (-1210)
			BKC	3248 (-1488)
			Congl.	3314 (-1554)
			Arbuckle	3417 (-1657)
			LTD	3437 (-1677)

RELEASED
 SEP 0 1982
 FROM CONFIDENTIAL
 RECEIVED
 AUG 13 1982
 CONSERVATION DIVISION
 Wichita, Kansas

Report of all strings set— surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	247'	Common	130 sx.	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF
	Water %	Gas-oil ratio
Disposition of gas (vented, used on lease or sold)		CFPB
	Perforations	

Sun-Oilwell Cementing
A Division of BJ Hughes, Inc.

P. O. Box 169
GREAT BEND, KANSAS 67530

CEMENTING TICKET
and Invoice Number

No. 12011

15-167-21958-00-00

Date 8-1-82	Customer Order No.	Sec. 11	Twp. 12S	Range 14W	Truck Called Out 7:40	On Location 6:00	Job Began	Job Completed 12:15 PM
----------------	--------------------	------------	-------------	--------------	--------------------------	---------------------	-----------	---------------------------

Owner Gunsa Williamson	Contractor Ed Tap	Charge To
Mailing Address	City	State

Well No. and Farm J. Hays #1	Place Y2F N 2A	County Lincoln	State
---------------------------------	-------------------	-------------------	-------

Depth of Well 2440	Depth of Job	Casing New	Size Weight	Size of Hole Amt. and Kind of Cement	Cement Left in casing by	Request Necessity	feet
-----------------------	--------------	---------------	----------------	--	-----------------------------	----------------------	------

Kind of Job PTH	OW (NW)	Drillpipe 2 1/2	Rotary Cable	Truck No.
--------------------	------------	--------------------	-----------------	-----------

Condition of Well at time of Cementing: Normal Typ of Plugs: _____

Pressure Circulating _____ Minimum _____ Maximum _____

Time Required Mixing Cement _____ min. Making Change _____ min. Pumping Cement _____ min.

Remarks: amt. 120 SK 50%
60 SK at 600'
40 SK at 300'
10 SK at 40'
10 SK Put in 10'

Price Reference No.	4
Price of Job	370.00
Second Stage	
Standby Truck	
Other Charges	
Pump Truck Mileage	13.50

RECEIVED
STATE CORPORATION COMMISSION
AUG 09 1982
CONSERVATION DIVISION
Wichita, Kansas

Cement Phil H. Charnick	Material Left on Location	1/2
Helper Mark Jim	District	Howe
The above job was done under supervision of the owner, operator, or his agent whose signature appears below.		State Kansas

Prices Subject to Correction. _____ Agent of Contractor or Operator

SALES TICKET FOR MATERIALS

QUANTITY SACKS	BRAND AND TYPE	PRICE	TOTAL
60	10 AM 10 17	7.75	
10	Poz	1.10	
Cc. Cl.	30R TH	1.21	
AM. Cl.			
Gel	20R TH		
Plugs	YSA 1 Day hole		
Delivered by Truck No.	R 21	Handling and Dumping	
Delivered From	Ringwell	Mileage	9.4
Signature of Operator	Tim	Sales Tax	
		Total Charges	