

4-041659

2-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-167-22,298 - 00-00

NW SW NE /4 SEC. 17, 12 S, 14 W
3630 feet from S section line
2310 feet from E section line

Operator license# 5146 Lease Steckel "E" well # 2

Operator: Rains & Williamson Oil Co., Inc. County Russell

Address: 220 W. Douglas Suite #435 Wichita, Kansas 67202
Well total depth 3130 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 261 feet w/160 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing - Express Well Service License# -

Address: Hays, Kansas 67601 - Victoria, Kansas 67671

Company to plug at: Hour: 9:00A.M. Day: 23 Month: February Year: 95

Plugging proposal received from: A.D. Belt

Company: Rains & Williamson Oil Co., Inc. Phone:

Were: 5 1/2" casing set @ 3129' w/150 sxs. cmt. Perf. @ 2816' - 2886'.
Salt @ 1400' - Anhy. @ 693' - Dakota @ 300' - W.L.M. 1968'.
D.V. at 740' circulate surface with 340 sxs. cement. Tubing fish at 1150'.
Rods and pump out of hole. Ordered 375 sxs. 60/40 pozmix - 6% gel with 1/4# F.C. plus 300# hulls

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:00P.M., Day: 23, Month: February, Year: 95

Actual plugging report: R.I.H. with tubing to set EZ-SV at 984'.
Squeezed 175 sxs. 60/40 pozmix - 6% gel - sting out of EZ-SV and circulated cement to surface with 35 sxs. cement. P.O.O.H. with tubing.
Squeezed casing with additional 165 sxs. cement. Max. P.S.I. 400#. S.I.P. 100#. 8 5/8" S.P. Pressured-up to 300# - no cement pumped.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

I did [X] / did not [] observe the plugging. Dennis L. Hamel

(agent)

Form CP-2/3

DATE 3-9-95

INV. NO. 42237

2-23 APR 25 1995

03-06-95