

6010159

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-22373-00-00

NE, SEC. 17, T. 12 S, R. 14 W/4

2310 feet from N section line

990 feet from W section line

AUB
KCC

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Steckal Well # E-3

Operator: Rains & Williamson

County Russell

Name & Address 220 W. Douglas

Well Total Depth 3090 100.43 feet

Wichita Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson License Number 5146

Address Same

Company to plug at: Hour: 1 AM Day: 2 Month: 7 Year: 19 84

Plugging proposal received from Larry Hindenlifer

(company name) Rains & Williamson (phone) 800 362-2290

were: order 170 sx. cement 50/50 pozmix 690 gal. 390 c.c.

1 sx hulls. 1-8 5/8 plug 1-sx. Flow Seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 1621 Anhydrite 689-725 Arbuckle No

Dakota. 1575 Plugging Proposal Received by Dale F. Balthazor

46 = 350

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part (None)

Operations Completed: Hour: 1:45 AM Day: 2 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 700' for 10 mi.

50 sx. @ 700

100 sx. @ 400 mixed with 1sx. Flow Seal.

dumped 1sx. hulls pushed plug to 40'

10 sx @ 40

10 sx @ in Rat Hole

Remarks: Cementing Co. Sun

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

7-18-84

Signed Dale F. Balthazor
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

07-09-81
1111 09 1981

CONSERVATION DIVISION
Wichita, Kansas

July 6th
22