

4 060028

15-167-22878-00-00
11-9

STATE CORPORATION COMMISSION

11-20-89
NOV 20 1989

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-22,878-00-00
S2 SW SE, SEC. 20, T. 12 CONSERVATION DIVISION
Wichita, Kansas W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 6194

Operator: ESP Development
Name & Address RR #1 Box 18
Paradise, KS 67658

330 feet from S section line
1980 feet from E section line

Lease Name Paradise South Well # 1
County Russell
Well Total Depth 3230 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXX

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling License Number 4083

Address Hays, KS

Company to plug at: Hour: 7:00AM Day: 9 Month: November Year: 19 89

Plugging proposal received from Frank Taggart
(company name) Western Kansas Drilling (phone) 913-628-2296

were: Space all plugs with heavy drilling mud through drill pipe.

Order 165 sx 60/40 pos 6% gel 1/4# floccel per sx.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXXX

Operations Completed: Hour: 7:00AM Day: 9 Month: November Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3192' with 20 sxs. Arbuckle 3192'
2nd plug at 800' with 20 sxs. Anhydrite 778-810'
3rd plug at 425' with 100 sxs. Dakota 125-425'
4th plug at 40' with 10 sxs. Surface pipe to 220'
rathole with 15 sxs.

Remarks: Allied Cementing
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-89
INV. NO. 26550
J.H.S

Signed Herb Deines
(TECHNICIAN)
Herb Deines