

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21,800 - 001-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Ks. 67202

Lease Name Bar S Ranch Well No. #1

Location SE-SE-NW Sec. 4 Twp. 12 Rge. 14 (East) (West)

County Russell Total Depth 3447'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rains & Williamson Oil Company, Inc.

Address 435 Page Court, 220 W. Douglas, Wichita, Ks. 67202 License No.

Operation Completed: Hour: 6:00PM Day: 14th Month: Nov. Year: 19 81

Plugging Operations attended by Agent?: All Part None XX

The above well was plugged as follows: .

8 5/8"-245' s.p. cuc. w/160 sacks common cement-60/40 posmix-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 660' w/70 sacks cement

2nd plug @ 150' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulated with 10 sacks of cement in rat hole.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 12-17-81
INV. NO. 5777-60