

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21,958 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 226 W. Douglas, Suite 435, Wichita, Kansas 67202

Lease Name Juhn Well No. 1

Location SE SE SW Sec. 11 Twp. 12 Rge. 14 (~~East~~) (West)

County Russell Total Depth 3432'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Co. Tools and Sun Oilwell Cementing

Address _____ License No. _____

Operation Completed: Hour: 12:15 PM Day: 1 Month: August Year: 1982

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows: Top ~~Depth~~ Anhydrite 901

Hole circulated and Filled with mud. 60 sacks cement pumped through drill pipe at 600'. 40 sacks cement pumped through drill pipe at 300'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 09 1982
CONSERVATION DIVISION
Wichita, Kansas
08-09-82

Cement used: 50/50 Pozmix w/2% gel and 3% cc.

Amount of Surface Casing: 8 5/8" - 266' - circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

RECEIVED
DATE 8-19-82
NO. 942-W