

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE-SW-SF

SEC. 16 TWP. 12 RGE. 14 W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Heard. A DUB KCC

Operator Shields Oil Producers Address Russell, Kans.

Field \_\_\_\_\_ County Russell

Total Depth 3320' Feet.

Plugging Contractor Shields Oil Producers

Plugging Contractor's License No. \_\_\_\_\_

Address Russell, Kans.

(Describe briefly the manner in which the well was plugged)

*Surface pipe - 7000. 20" @ 22' - 15 1/2" @ 335' -  
12 1/2" @ 581' - 10" @ 885' - 8 3/8" @ 2520' & 7" @ 3110'  
Ripped off shot joint on 7" & started to pull same.  
after pipe was free stopped & filled hole w/ heavy  
mud. Stopped @ intervals & kept hole fully mud.  
same process on all pipe pulled. Set R.B. @ 335' &  
summed 60 st. cem. Then filled w/ heavy mud to 35'  
ground by set R.B. & pumped 30 st. cem. to base of cellar.*

Victor G. Gans  
District Conservation Agent

07-19-55

DATE 7-16-55

**PLUGGING**  
FILE SEC. 16 TWP. 12 R. 14 W  
BOOK PAGE 135 LINE 31