

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 17-23

LOCATION SW SWCSW

SEC. 22 TWP. 12 RGE. 14

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Wagner

Operator Franco Central Oil Address Wichita, Kans

Field _____ County Russell

Total Depth 3268 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 217' circulated with cement - 5 1/2" at 3258 cemented.
Lane-wells plugs to 3030', tap perforations at 2680'.
Filled with chat to 2070', run 4 sax cement with dump bailer.
pulled 2595' 5 1/2", filled hole with mud to 210', set rock bridge and
15 sax cement, filled with mud to 40', set rock bridge and 10 sax
cement to bottom cellar.

08-14-50

PLUGGING
FILE SEC 22 TWP 12 R 14
BOOK PAGE 17 LINE 22

[Signature]
District Conservation Agent

Date 8-12-50