

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SE

SEC. 22 TWP. 12 RGE. 14 ^W

Dry Hole Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Wagner-Wagner ^{AMB²}
Operator Gough W. Davis Address Wichita, Kans ^{301 South Clifton}
Field _____ County Russell
Total Depth 3276 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 254' circulated with cement- 5 1/2" at 3275' with
135 sax cement behind.

lane-wells plugs and cement to ~~3000~~ 3000', top perforations at
2960', filled with chat to 2950', set 4 sax cement with dump bailer,
pulled 2542' 5 1/2", filled hole with heavy mud to 250', set rock
to 240', set 15 sax cement, filled with mud to 40', set
rock bridge and 10 sax cement to bottom cellar.

08-02-50
AUG 2 - 1950
STATE CORPORATION
COMMISSION
PLUGGING
FILE SEC 22 T 12 R 14
BOOK PAGE 19 LINE 14

[Signature]
District Conservation Agent

Date 7-30-50

F