

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 67-44

LOCATION NE NE SW

SEC. 22 TWP. 12 RGE. 14

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease ~~Wagoner~~ Wagner Aubree

Operator France Central Oil Address Wichita, Kans

Field _____ County Russell

Total Depth 3338 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 227' circulated with cement - 5 1/2" at 3037' with 150
sax cement behind, Cement and Baker plugs to 3040', top perforations
at 2996'

Filled with chat to 2990', set 4 sax cement with dump bailer,
pulled 2020', 5 1/2", filled hole with mud to 220', set rock bridge
and 15 sax cement, filled with mud to 40', set rock bridge and 10
sax cement to bottom cellar.

04-10-51

Judson Petty
District Conservation Agent

Date 4-5-51

PLUGGING
FILE SEC 22 12 R14W
BOOK PAGE 67 LINE 44