

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED FORM CP-3
STATE CORPORATION COMMISSION
OCT 07 1982
CONSERVATION DIVISION
Wichita, Kansas
1-8-82
10-07-82

API Number 15-167-21,998 ✓ *[Signature]*

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address 7701 E. Kellogg, Suite 780, Box 18407, Wichita, Ks. 67218 #5131

Lease Name Teppe Well No. 1

Location NE NW NE Sec. 28 Twp. 12 Rge. 14 (East) (West) (West)

County Russell Total Depth 3215'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird Drilling, Inc.

Address 7701 E. Kellogg, Suite 780, Box 18407, Wichita, Ks. 67218 License No. 38

Operation Completed: Hour: 6:30 PM Day: 25 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 441' S.P. cwc. w/225 sacks common - 2% Tel. - 3% Col. Cl.

Ordered 140 sacks ⁵⁰/₅₀ posmix - 4% Tel. - 3% Col. Cl. & 8 5/8" plug.

Spot w/drill stem w/ heavy mud between all plugs.

1st plug @ 660' w/80 sacks.

2nd plug @ 450' w/40 sacks

3rd plug - solid bridge of balls & plug @ 40' w/10 sacks.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 441' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.
Signed: *[Signature]*
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED
DATE 10-20-82
NO. 1462-W

INVOICED
DATE _____
INV. NO. _____